



15-153-20088-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1970
CONSERVATION DIVISION
Wichita, Kansas
10-14-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clyde Jones of Skelly Oil Company has this date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name: Rosa Dozbaba Well No. 3-A

Location: 60' W of CNE-NW Sec. 15 Twp. 1 Rge. (E)(W) 3h

County: Rawlins Total Depth 4343' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jones was instructed to plug the well as follows:

370'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1900'.

Circulate hole with heavy mud. Pull DP to 2125' and displace 100 Sx.
cement thru DP. Pull DP to 390' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Fehole
Conservation Division Agent