



15-153-30068-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 20 1966

10-20-66

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company.

Complete Address: 650 Fourth National Bank Building, Wichita, Kans.

Lease Name: Horinek Well No. B-3

Location: CSE-SW Sec. 12 Twp. 1 Rge. (E)(W) 34

County Rawlins Total Depth 4247 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Helberg was instructed to plug the well as follows:

262' -- 8 5/8" surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	250' with 1/2 sk. hulls & 20 Sx. cement.
"	"	40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent