

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.--82-3-117

15-153-20173-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Cahoj Supply Well

WELL NUMBER \_\_\_\_\_

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line  
 C SW SW

SEC. 15 TWP. 1 RGE. 34W(E)or(W)

COUNTY Rawlins

Date Well Completed 4-18-74

Plugging Commenced 10-14-87

Plugging Completed 10-22-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

2915 Classen Blvd. Suite 300

ADDRESS Oklahoma City, Okla. 73106

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well Water Supply

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2801'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	304'	none
				7"	2800'	412'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 2200' and 7 sacks cement. Shot pipe @1508',  
821', 708', 628', 515', 412', pulled a total of 15 joints of 7" casing. Plugged  
surface with 5 hulls and 200 sacks econlite. Plugging Complete.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 87

*Irene Hoover*  
 Notary Public  
 STATE CORPORATION COMMISSION

My Commission Expires: \_\_\_\_\_



OCT 29 1987 Form CP-4  
 10-29-87 Revised 07-86  
 CONSERVATION DIVISION  
 Wichita, Kansas