

15-153-20079-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Rosa Dozbaba

WELL NUMBER A-2

_____ Ft. from S Section Line

_____ Ft. from E Section Line

1980' FNL & 1980' FWL
SEC. 15 TWP. 1 RGE. 34W (E) or (W)

COUNTY Rawlins

Date Well Completed _____

Plugging Commenced 8-25-87

Plugging Completed 9-3-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

ADDRESS 2915 Classen Blvd. Suite 300
Oklahoma City, Ok. 73106

PHONE# 405 525-3371 OPERATORS LICENSE NO. 5988

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	372'	none
				5-1/2"	4299'	1994'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3950' and 5 sacks cement. Shot pipe @2430', 1994', pulled a total of 64 joints of 5-1/2" casing. Plugged surface with 5 sacks hulls and 200 sacks econolite.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso **RECEIVED**
STATE CORPORATION COMMISSION
SEP 9 4 1987
CONSERVATION DIVISION
Wichita, Kansas

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 9th day of Sept., 19 87


Irene Hoover
Notary Public

My Commission Expires:



15-153-20079-00-00
SKELLY OIL COMPANY

Well Record



Lease Name and No. Rosa Dozhaba "A" #64413 Well No. 2
Lease Description NW/4 Section 15-15-34W, Rawlins County, Kansas

Location Staked June 15 19 70 by Laughlin-Simmons
1980 feet from North line 1980 feet from West line
of Section 15-15-34W, Rawlins County, Kansas

Elev. K.B. 3123'
Elev. G.L. 3118'

Drilling Contractor Gabbert-Jones, Inc., Wichita, Kansas

Work Com'd. June 16, 19 70 Drilling Com'd. July 2, 19 70 Reached Total Depth July 9, 19 70

Rotary Drilling from Surface to 4300' Cable Tool Drilling from _____ to _____

Well Completed July 24, 19 70 Total Depth 4300' P.B.T.D. 4272'

Initial Completion Test August 6 19 70 State Potential Test - POB 24 hours, 196 BO & 12 BW

Pressures: F.C.P. _____ F.T.P. _____ S.I.C.P. _____ S.I.T.P. _____

PRODUCING FROM

LANSING-KANSAS CITY FORMATION	thru	PERFORATIONS	4036'	4212'	Total No. Shots	39
FORMATION	thru	OPEN HOLE PERFORATIONS	TOP	BOTTOM	Total No. Shots	
FORMATION	thru	OPEN HOLE PERFORATIONS	TOP	BOTTOM	Total No. Shots	

CASING RECORD

STRINGS	SIZE	WHERE SET (Depth)	CEMENTING RECORD		All Measurements were taken from top of Kelly Bushing which is <u>5</u> ft. from top of surface casing Electric Collar
			Sacks Used	Top Cem's Bh'd. Cas'g.	
Surface	8-5/8"	372'	250	Surface	
Intermediate					
Production	5-1/2"	4299'	300	?	
Liner					Top Liner:

Size	Wt.	Thds.	Kind	Cond.	Jts.	LEFT IN				PULLED OUT			
						LTM		WTM		LTM		WTM	
						Feet	In.	Feet	In.	Feet	In.	Feet	In.
8-5/8"	20#	8R	L. B. Foster R3 A		9	365		367					
5-1/2"	14#	8R	J-55 SS R-2	C	138	4293		4326					

SIGNIFICANT GEOLOGICAL FORMATIONS

NAME	TOP	BOTTOM	GAS		OIL		REMARKS
			FROM	TO	FROM	TO	
Source: Schlumberger							
Stone Corral	2955'						
Topeka	3803'						
Oread	3220'						
Douglas	3977'						
Lansing-K.C.	4014'				4036'	4212'	Effective pay by electric loss

TREATMENT RECORD

DATE	TYPE TREATMENT	INTERVAL TREATED	AMOUNT OF TREATMENT

WORKOVER RECORD

TYPE WORK	DATE COM'D.	DATE COMP.	Plugged back or Deepened		PROD. BEFORE	PROD. AFTER
			FROM	TO		

See Reverse for detail information

8-3-87
Wichita, Kansas

49336
1/8/77