

15-193-30068-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rawlins County. Sec. 12 Twp. 1S Rge. 34 ~~XXXXX~~(W)

Location as "NE/CNW/SW" or footage from lines. C SE SW
Lease Owner Empire Drilling Company
Lease Name Horinek "B" Well No. 3
Office Address 650 4th Natl. Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 18 19 66
Application for plugging filed October 18 19 66
Application for plugging approved October 18 19 66
Plugging commenced October 18 19 66
Plugging completed October 18 19 66
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Shale	0	280	8 5/8"	263'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 600' with 20 sacks cement.
Plug set at 250' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1966

CONSERVATION DIVISION
Wichita, Kansas

10-24-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 4th Natl. Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 4th Natl. Bank Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 19 66

My commission expires September 14, 1968.
Sandra Kay Peer
Sandra Kay Peer Notary Public.

LOG

15-153-30068-00-00

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Horinek "B" #3
 LOCATION: C SE SW Section 12-1S-34W, Rawlins County, Kansas
 COMMENCED: October 8, 1966 ELEVATION: 3096 KB
 COMPLETED: October 18, 1966 POTENTIAL: D & A

0	to	280	Surface-Shale
280	to	450	Shale
450	to	1550	Shale & Bentonite
1550	to	2240	Sand-Shale
2240	to	2410	Sandy Lime & Gypsum
2410	to	2517	Sand & Shale
2517	to	2735	Shale - Gypsum
2735	to	2941	Shale
2941	to	2974	Anhydrite
2974	to	2987	Shale & Shells
2987	to	4247	Lime & Shale
4247			Rotary Total Depth

SET: 263' of 8 5/8" with 150 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

Anhydrite	2945	+151
Base Anhydrite	2976	+120
Wabaunsee	3627	-531
Topeka	3799	-703
DeerCreek	3840	-744
Oread	3910	-814
Base Leavenworth	3958	-862
Douglas Sand	3964	-868
Lansing	4000	-904
Sandy Zone	4019	-923
Total Depth	4250	-1154


RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1966
 10-24-66
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Horinek "B" #3, C SE SW Section 12-1S-34W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 24th day of October, 1966.


 Sandra Kay Peer, Notary Public

My commission expires September 14, 1968.