

15-193-20419-00-00

LEASE NAME Ruda

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 7

4620 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 13 TWP. 1S RGE. 33 (E) or (W)

COUNTY Rawlins

Date Well Completed 5-81

Plugging Commenced 9-6-95

Plugging Completed 9-6-95

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 21, 1995 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation L-KC Depth to Top 4166' Bottom 4258' T.D. 4302'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil, Water	0	297	8 5/8"	297	0
		0	4324	5 1/2"	4324	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
DV Tool @ 3023' w/500 sx HLC to surface. Pumped down 5 1/2" casing: 350 sx 60/40, 6% gel, 5 sx hulls in first 15 sx cement. Pump 50 sx 60/40, 6% gel down 8 5/8-5 1/2" annulus to pressure. Plugging complete.

Name of Plugging Contractor Halliburton Company License No. _____


Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheurman (Employee of Operator) ~~XXXXX~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Scott W Scheurman
(Address) P.O. Box 2757, Wichita, KS 67201-2757



SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 95

Rebecca K. Crawford
Notary Public

My Commission Expires: 1-13-99

USE ONLY ONE SIDE OF EACH FORM