

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,219-0000

LEASE NAME Ruda

WELL NUMBER #6

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 13 TWP. 1S RGE. 34 ~~XX~~ or (W)

COUNTY Rawlins

Date Well Completed Nov. 1975

Plugging Commenced 8-27-87

Plugging Completed 8-27-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, #1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6 - Carl Goodrow

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4006' Bottom 4300' T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing</u>	<u>Oil, water</u>	<u>0</u>	<u>323</u>	<u>8 5/8"</u>	<u>316'</u>	<u>None</u>
		<u>0</u>	<u>4299</u>	<u>5 1/2"</u>	<u>4294'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 5 sx Halls, 130 sx Econolite cement down 5 1/2" casing. Shut-in with 1000# pressure. Pumped 95 sx Econolite cement down 8 5/8" - 5 1/2" annulus. Shut-in with 450# pressure. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 7718

Address Oberlin, KS 67749

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~xxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman


(Address) 125 N. Market, #1750, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 87

Rebecca K. Crawford
 Rebecca K. Crawford Notary Public

My Commission Expires: 1-7-91

RECEIVED
 STATE CORPORATION COMMISSION



Form CP-4
 Revised 08-84
 SEP 9 1987
 9-9-87
 CONSERVATION DIVISION
 Wichita, Kansas

WELL LOG 15-153-20219-00-00

COMPANY Empire Drilling

SEC. 13 T. 1S R. 34W

FARM RUDA NO. 6

LOC. NE NW

RIG. NO. 3


TOTAL DEPTH 4300'

COUNTY Rawlins
KANSAS

COMM. 10/21/75

COMP. 10/30/75

CONTRACTOR Murfin Drilling



CASING

20	10
15	5 5/8" @ 323' w/200 SX
12	6
13	5 1/2" @ 4299' w/125 SX

ELEVATION 3109

PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

270 - clay, sand
1100 - shale
1175 - sand
2610 - shale, sand
2785 - shale
3250 - shale, sand
3566 - shale
4065 - lime, shale
4077 - coring
4104 - lime, shale
4114 - coring
4161 - lime, shale
4181 - coring
4193 - lime, shale
4214 - coring
4300 - shale, lime
4300 - TD