

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD #4
 K.A.R.-82-3-117

15-153-20059-00-01

API NUMBER _____

LEASE NAME Ruda

WELL NUMBER 5W

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 13 TWP. 1S RGE. 34 (X)or(W)

COUNTY Rawlins

Date Well Completed 11/69

Plugging Commenced 10-17-88

Plugging Completed 10-17-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, Suite 1750

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-13-88 (date)

by Carl Goodrow, District 4 (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? See plugging application

Producing Formation Lansing Depth to Top 4023' Bottom T.D. 4280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION
 10-25-88
 OCT 25 1988
 CONSERVATION DIVISION
 Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil, Water	0	4279	5 1/2"	4279	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mix and pump 225 sx Halliburton HDL down 5 1/2" casing, 5 sx cottonseed hulls mixed with first 15 sx cement. Final casing pressure 210 psi. Mix and pump 25 sx Halliburton HDL down 8 5/8"-5 1/2" annulus. Final annulus pressure 150 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 7718

Address Box 47, Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) 125 N. Market, #1750, Wichita, KS 67202

STATE OF KANSAS
 NOTARY PUBLIC
 REBECCA K. CRAWFORD
 State of Kansas
 My Appt. Exp. _____

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1988

Rebecca K Crawford
 Notary Public

My Commission Expires: 1-7-91

DRILLER'S LOG

COMPANY: EMPIRE DRILLING
 CONTRACTOR: LEBEN DRILLING
 FARM: RUDA #5
 LOCATION: C SW NW SECTION 13-1S-34W
 RAWLINS COUNTY, KANSAS
 COMMENCED: 10-30-69
 COMPLETED: 11-7-69
 Elevation - 3129 ^{ft}

0	156	Clay
156	241	Sand
241	1923	Sand & Shale
1923	1985	Shale
1985	2245	Sand & Shale
2245	2756	Shale
2756	2776	Blains
2776	2964	Shale & Red Bed
2964	3000	Anhydrite
3000	3090	Shale
3090	3570	Lime & Shale
3570	4279	Lime
	<u>4279</u>	<u>RTD</u>

8 5/8" 24# used surface casing set @ 312' cemented with 175 sacks common 2X C.C.

I, James R. Rodgers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ruda #5 Well, located C SW NW of Section 13, Township 1 South, Range 34 West, Rawlins County Kansas, as reflected by the records of Leben Drilling, Inc.

James R. Rodgers
James R. Rodgers

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 2nd day of December, 1969.

Helen L. Lindennuth
Helen L. Lindennuth

My Commission Expires;
November 13, 1974

RECEIVED
STATE CORPORATION COMMISSION
JUN - 3 1969
CONSERVATION DIVISION
Wichita, Kansas