

15-153-30067-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Completion 8-66

LEASE NAME Horinek "B"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 12 TWP. 1s RGE. 34 (X) or (W)

COUNTY Rawlins

Date Well Completed 8-66

Plugging Commenced 11-14-89

Plugging Completed 11-16-89

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 16, 1989 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? See plugging application

Producing Formation L-KC Depth to Top 4068 Bottom 4252 T.D. 4285

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L-KC	oil	0'	289'	8 5/8"	282'	0'
		0'	4320	5 1/2"	4313'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mix and pump down 5 1/2" - 225 sx HDL, 1/4# Flocele, 400# hulls. Mix and pump 25 sx HDL and 100# hulls down 8 5/8"-5 1/2" annulus. Shut-in pressure 250#. Plugging complete. Carl Goodrow on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. n/a

Address Oberlin, KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) 125 N. Market, #1750, Wichita, KS



RECEIVED STATE CORPORATION COMMISSION FEB 28 1990
I, Rebecca K. Crawford Notary Public, do hereby certify that Scott W Scheuerman has been and sworn to before me this 27th day of February, 19 90.

My Commission Expires: 1-7-91

15-153-30067-00-00

LOG

COMPANY: Empire Drilling Company
CONTRACTOR: Empire Drilling Company
FARM: Horinek "B" #1
LOCATION: SW SW Section 12-1-34, Rawlins County, Kansas
COMMENCED: July 26, 1966 **ELEVATION:** 3119 KB
COMPLETED: August 8, 1966 **POTENTIAL:** Producer

0	to	308	Surface-Sand-Shale
308	to	1360	Shale
1360	to	2000	Shale & Shells
2000	to	2252	Shale - Gypsum
2252	to	2530	Shale & Sand
2530	to	2684	Blaine gypsum & Shale
2684	to	2750	Shale & Lime
2750	to	2755	Shale
2755	to	2769	Gypsum
2769	to	2959	Redbed
2959	to	2993	Anhydrite
2993	to	3275	Shale & Shells
3275	to	4395	Lime & Shale
4395	to	4426	Lime & Chert
4426	to	4580	Lime & Shale
4580	to	4635	Shale-Lime-Chert
4635	to	4660	Cherty Conglomerate
4660			Rotary Total Depth

SET: 289' of 8 5/8" with 125 sacks cement.
 4310' of 5 1/2" with 125 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

Topoka	3811	-692
Dear Creek	3851	-732
Oread	3923	-804
Leavenworth	3968	-849
Douglas Sand	3976	-857
Lansing	4012	-893
Sandy Zone	4032	-913
Base Kansas City	4270	-1151
Top of Cherokee	4445	-1326
Top of Conglomerate	4614	-1495
Top of Granite	4658	-1539
Log Total Depth	4660	


RECEIVED
 STATE CORPORATION COMMISSION
 NOV - 1 1966
 11-1-89
 CONSERVATION DIVISION
 Wichita, Kansas

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Horinek "B" #1, SW SW Section 12-1-34, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 16th day of August, 1966.


 Sandra Kay Peer, Notary Public

My commission expires September 14, 1968.