

U
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-0527600-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964
12-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sinclair Oil & Gas Company,

Complete Address: Box #456, Plainville, Kansas.

Lease Name Bartosovsky Well No. 1

Location CSW Sec. 8 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4339

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00PM Day 28 Month 12 Year 1963

The Above well was plugged as follows:

449'--8 5/8" Surface pipe, cement circulated. 4339'--5 1/2" production casing cemented with 200 Sx. Well plugged back to 4283', top perforations @ 4165'.

Sanded well back to 4150' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" to 660' and attempted to circulate heavy gel mud, pumped in 10 Sx. gel but hole would not circulate. Pulled 5 1/2" to 450', pumped in 5 Sx. gel, hole would not circulate. Pulled 5 1/2" to 420' and displaced 10 Sx. cement thru 5 1/2". Pulled 5 1/2" to 270' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set 5' bridge @ 40' and 10 Sx. cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1/3/64
INV. NO. 8409-u

Signed: M. L. Nichols
Well Plugging Supervisor