

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1973
08-06-1973
CONSERVATION DIVISION
Wichita, Kansas

15-153-20167-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Bartosovsky Well No. 1

Location App:-CSE-SE-SW Sec. 8 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4245'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 10:00 PM Day 2 Month 8 Year 1973

The above well was plugged as follows:

269'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1925'.

Circulated hole with heavy mud. Pulled DP to 2150' and displaced 110 Cu. Ft. cement
thru DP from 2150' to 1825'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 8/8/73
INV. NO. 7724-W