

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20089-00-00

Operator's Full Name Argosy Petroleum Company,

Complete Address 405 Walltowers East, Midland, Texas. 79701

Lease Name Sramek Well No. A-2

Location CSW-SE Sec. 7 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4300'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 12:00 PM Day 12 Month 10 Year 1970

The above well was plugged as follows:

268'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 100 Sx. cement thru
DP from 2100' to 1775' with 100 Sx. Pulled DP to 275' and displaced 25 Sx. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 10-15-70

INV. NO. 2684-W