

15-153-00037-00-02

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

~~15-153-00037-00-00~~

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963
12-26-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address: Box #649, McCook, Nebraska.

Lease Name Cahoj Well No. C-1

Location SE-SE-NE Sec. 8 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4350

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 5:45PM Day 18/12 Month 12 Year 1963

The Above well was plugged as follows:

445'--8 5/8" Surface pipe, cement circulated. 4350' 5 1/2" production casing cemented with 300 Sx. Well plugged back to 4187'. Top perforations from 3578' to 3584'.

Sanded well back to 3570' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" to 480' and circulated heavy gel mud (15 Sx. gel). Displaced 20 Sx. cement thru 5 1/2" @ 480'. Pulled 5 1/2" to 330' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set 5' rock bridge @ 35' and 10 Sx cement to bottom of cellar. (Recovered 2280' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

NOTICED

DATE 12-26-63

INV. NO. 8344-w

Signed: W. L. Nichols
Well Plugging Supervisor