

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

#4 WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,016-00-00

LEASE NAME Horinek "B"

TYPE OR PRINT

NOTICE: Fill out **completely**
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #4

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Gore Oil Company

SEC. 11 TWP. 1S RGE. 34 (E) or (W)

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

COUNTY Rawlins

PHONE# (316) 263-3535 OPERATORS LICENSE NO. 5552

Date Well Completed 3/68

Character of Well oil

Plugging Commenced 4/19/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/19/93

The plugging proposal was approved on 4/19/93 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation L-KC Depth to Top 4094' Bottom 4232' T.D. 4275'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L-KC	Oil, water	0	268	8 5/8"	268	---
		0	4265	5 1/2"	4265	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump down 8 5/8" - 5 1/2" annulus - 25 sx HLC, 4% add gel, 1/4#/sx flocele to pressure.
Pump down 5 1/2" casing - 400 sx HLC, 4% add gel, 1/4#/sx flocele, 500# hulls. Max pressure 100 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Oberlin

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company


STATE OF Kansas COUNTY OF Sedgwick, ss. MAY 19 1993 5-19-93

Scott W Scheuerman

(Employee of Operation of _____) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757



SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 93

1-7-95

Rebecca K. Crawford
 Notary Public

My Commission Expires: 1-7-95

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

Empire Drilling Co.
LEBEN DRILLING, INC.
HORENIK B-#2/
C SE SE SECTION 11-1S-34W
RAWLINS COUNTY, KANSAS
3-4-68
3-15-68

COMMENCED:
COMPLETED:

0	250	Clay, Sand
250	1960	Shale
1960	2211	Shale, Shells
2211	2605	Shale
2605	2731	Shale, Redbed
2731	2750	Anhydrite
2750	2933	Shale
2933	2969	Anhydrite
2969	2984	Shale
2984	3585	Shale, Lime
3585	3915	Lime, Shale
3915	3925	Lime
3925	4055	Lime, Sand
4055	4275	Lime
	<u>4275</u>	<u>RTD - Set 5 1/2" Casing</u>

8 5/8" 8 rd. 24# used surface casing set @ 267' cemented with 160 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Horenik B-#2 Well, located C SE SE of Section 11, Township 1 South, Range 34 West, Rawlins County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public and for Barton County, Kansas, this 19th day of March, 1968.

Ulanda Nichols

Ulanda Nichols

RECEIVED
REGISTRATION COMMISSION
MAR 30 1968
CONSERVATION DIVISION
Wichita, Kansas

3-30-93

My Commission Expires:
April 1, 1971