

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20100-00-01
LEASE NAME TEXACO CAHOJ UNIT

WELL NUMBER 12

NOTICE: Fill out completely 4620 Ft. from S Section Line
and return to Cons. Div. 4620 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 9 TWP. 1S RGE. 34W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY RAWLINS
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 6/12/70
Character of Well INJ (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 11/01/01
Plugging Completed 11/01/01

The plugging proposal was approved on 11/01/01 (date)
by Carl Goodrow w/KCC Hays, KS. (KCC District Agent's Name).
Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation _____ Depth to Top 3987 Bottom 4193 TD 4268' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	372	8 5/8	372	0
		production	4267	5 1/2	4267	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Pumped 140 sxs 60/40 poz 10% gel & 500# hulls. Circ cement to surface. TOH w/tbg. Pumped 50 sxs (same) down 5 1/2" csg/ SI @ 300# Pumped 40 sxs down 8 5/8" SI @ 300#. Well P/A. Witnessed and approved by Carl Goodrow w/ KCC

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ss.


Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 4 th day of FEB., 2002.

Barbara J. Dodson
Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
FEB - 6 2002
KCC WICHITA

OR

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
11/1/01	3938

BILL TO
Murfin Drilling Co. Inc. PO Box 277 Logan, KS 67646

USED FOR PIA 36
APPROVED [Signature]

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	[REDACTED]	[REDACTED]	Rawlins		Injection	Abandoned	Lenny	PTA

PRICE REFERE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	110	2.50	275.00T
576W-P	Pump Charge	1	500.00	500.00T
329	Swift Ultra Light 60/40 Pozmix (10% gel)	350	5.85	2,047.50T
275	Cotton Seed Hulls	9	22.00	198.00T
581W	Service Charge Cement	470	1.00	470.00T
583W	Drayage	2,195.33	0.75	1,646.50T
	Subtotal			5,137.00
	Sales Tax		4.90%	251.71

Account	PLUG	W	No.	Amount	Description	
898 36		L	1069	[REDACTED]	Plug To ABANDON	* 12

Thank you for your business. **Total** \$5,388.71