

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-00013-00-00
Spot: SESESE Sec/Twnshp/Rge: 8-1S-34W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: CAHOJ TEXACO Well Number: 25
County: RAWLINS Total Vertical Depth: 4677 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4661 300 SX CMT
Surface Casing Size: 8.625 feet: 446 300 SX CMT

\$ 152⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2003 11:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-7514

Proposed Plugging Method: Ordered 240 sxs of Midcon II cement and 800# hulls.
Top down plug.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/23/2003 1:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 3917' - 4042'. Plugged off 4257' - 4260'. PBTD 4099'.
1970 - 5 1/2" casing squeezed at 2535' w/125 sxs.
1973 - 5 1/2" casing squeezed at 3065' w/150 sxs.
8 5/8" surface casing set at 446' w/300 sxs.
5 1/2" production casing set at 4661' w/300 sxs.
Connected to 5 1/2" production casing - pumped 245 sxs cement with 800# hulls.
Connectead to 8 5/8" surface casing - pumped 4 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
05-30-2003
MAY 30 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS CAHOJ A-1. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

100

Signed Darrel Dipman PIRT 1
(TECHNICIAN)

INVOICED

DATE 5-30-03
INV. NO. 2003061591

Form CP-2/3

MAY 27 2003

Cahoj #25

SKELLY OIL COMPANY

WKS #1 CAHOJ 'A'

8-1-34W

SE SE SE

Contr. C WENTWORTH DRLG

RAWLINS County

E 3141

Comm.

Comp. 7-3-59

IP

3000 BOPD/BOMB

| Tops | Depth | Datum |
|-----------|-------|-------|
| TOP | 3833 | -692 |
| LANS | 4018 | -877 |
| B/KC | 4290 | -1149 |
| MARM | 4321 | -1180 |
| CHERO | 4460 | -1319 |
| CHERO SND | 4542 | -1401 |
| MISS | 4644 | -1503 |
| WEA QTZ | 4660 | -1519 |
| PRE CAMB | 4670 | -1529 |
| TD | 4677 | -1536 |

Casing 8" 446 5" 4660
 DST 3804-86/1 HR, 45' M, BHP 1010#
 DST 3920-35/1 HR, 8' SL O SPK M, 1245#
 DST 3975-85/1 HR, 810' HO SPK SW, 1140#
 DST 4018-50/1 HR, 30' H OCM, BHP 1120#
 DST 4050-90/1 HR, 1' O, 4' OCM, BHP 80#
 DST 4086-4159/2 HR, 120' G, 5' O, 25' H OCM, 720#
 DST 4160-4230/2 HR, 3700' O, BHP 1320#
 DST 4230-80/1 HR, 6' OCM, BHP 750#
 DST 4534-60/1 HR, 2455' W, BHP 1140#
 PERF 4257-60: ACID 500: 260 BO/3 HR: PERF 4210-22: SWB 85 BOPH: PERF 4184-87: 4169-75
 SWB 50 BOPH: ACID 500: 100 BOPH: PB 4050:
 CAHOJ POOL PERF 4031-42: ACID 500: 35
 BOPH: GO 4275: PMP 21 BOPH & TR W/8 HR:

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WENTWORTH
 DRLG
 10/1/59