

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-05179-00-00  
Spot: SENESE Sec/Twnshp/Rge: 8-1S-34W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: CAHOJ TEXACO Well Number: 23  
County: RAWLINS Total Vertical Depth: 4230 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4341 250 SX CMT  
Surface Casing Size: 8.625 feet: 459 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2003 9:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC. #13748  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-7541

Proposed Plugging Method: Ordered 240 sxs of Midcon II cement and 800# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/23/2003 11:30 AM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Perforations 4021' - 4086'. PBTD 4130'.  
8 5/8" surface casing set at 459' w/400 sxs cement.  
5 1/2" production casing set at 4341' w/250 sxs cement.  
Ran tubing to 2500' - pumped 120 sxs cement with 400# hulls.  
Pulled tubing to 1200' - pumped 60 sxs cement with 350# hulls. Cement to surface.  
Pulled tubing to surface.  
Connected to 8 5/8" surface pipe - pumped 25 sxs cement w/50# hulls.  
Max. P.S.I. 75#.  
Connected to 5 1/2" casing - pumped 30 sxs cement.  
Max. P.S.I. 250#. S.I.P. 200#.

RECEIVED  
05-30-2003  
MAY 30 2003  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS CAHOJ A-2. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

100

Signed Darrel Dipman PIRT 1  
(TECHNICIAN)

INVOICED

Form CP-2/3

MAY 27 2003

5-30-03  
200 306 1591

CAHOJ #23

SKELLY OIL COMPANY W/O #2 CAHOJ 'A' 8-1-34W  
SE NE SE  
Contr. STERLING DRILLING RAWLINS County  
E-3126 Comm. \_\_\_\_\_ Comp. 12-25-59 IP 194 BOPD

Tops	Depth	Datum
OREAD	3900	-774
LANS	4004	-878
B/KC	4276	-1150
MARM	4306	-1180
TD	4341	-1215

Casing  
8" 459  
5" 4341  
DST 4200-12/1 HR, 5' OCM,  
2960' O, BHP 1180#  
PERF 2 1/4 4246-50: 1/3 BO & 5  
BW: PB 4240: 12/4200-02, 2 1/4  
4203-07: 2 1/4 4208-12: SWB 68  
BOPH/4 HR

CAHOJ POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MAOICER