

4-032175

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,107 -00-00

9-6

NW SW /4 SEC. 14 , 01 , 34 W  
1980 feet from S section line  
4620 feet from E section line

Operator license# 5552

Lease: Fikan "B" Well # 2

Operator: Gore Oil Company

County: Rawlins 140.07

Address: P.O. Box 2757  
Wichita, Kansas 67201-2757

Well total depth 4310 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 331 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 6 Month: September Year: 1996

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: -

Were: Order 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
KANSAS 10/3/96  
OCT - 2 A P 51

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

10-2-96

Completed: Hour: 12:00 P.M., Day: 6, Month: September, Year: 1996

Actual plugging report: 8 5/8" set at 331' cwc with 200 sxs. 5 1/2" set at 4305' with 150 sxs. D.V. set at 3100' cwc with 200 sxs cwc. Squeezed at 2900' w/200 sxs. Squeezed 5 1/2" w/350 sxs cement blend w/500# hulls mixed into Max. P.S.I. 250#. Held. Squeezed 8 5/8" w/50 sxs cement blend to Max. P.S.I. 300#. Blew hole in 8 5/8". Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

**INVOICED**

DATE 10-3-96

INV. NO. 46650

10