

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-05219-00-01  
Spot: CSESW Sec/Twnshp/Rge: 4-1S-34W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: CAHOJ TEXACO Well Number: 2  
County: RAWLINS Total Vertical Depth: 4334 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet: \$140.86  
Surface Casing: Size 8.625 feet: 367 300 SX  
Production: Size 5.5 feet: 4334 250 SX  
Liner: Size feet:

Well Type: EOR UIC Docket No: E16643.2 Date/Time to Plug: 02/22/2002 10:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perfs 4004' - 4198'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/22/2002 11:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 290 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 400#. S.I.P. 100#.  
Hooked up to backside and pumped 70 sxs.  
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED  
FEB 28 2002  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS KISLING A-1.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

FEB 26 2002

INVOICED

Form CP-2/3

DATE Feb 28 02

INVOICE NO. 2002061423

SKELLY OIL CO

#1

KISLING 9A

4-1-34W  
C SE SW

Contr.

RAWLINS

County

E 3101 RB Comm.

Comp.

5-20-60

IP

191 BOPD

Tops	Depth	Datum
ADM	3629	-528
TOP	3792	-691
OREAD	3880	-779
LANS	3993	-892
MARM	4291	-1190
TD	4334	-1233

Casing 8" 367 5" 4334

WLT 4237/1 HR, 13 CC WTR, BHP 1400#  
WLT 4192/1 HR, 200 CC O, 1600 CC W, 1065#  
WLT 4151/5", 50 CC M, BHP 795#  
WLT 3883/10", 75 CC W, BHP 1220#  
CO 4301: PERF 18/4230-33: BL NS/2 HR:  
ACID 250: SWB 7 B SW & TR 0/4 HRS: SWB  
9 B SW/4 HRS: TR 0: PB 4220: 24/4190-94  
SWB 32.2 B SW: 4195-98: SWB 19 B SW, TR  
0: PB 4180: 4149-52: 4164-65: NS: ACID  
250: SWB 244 BO & 2.4 B SW

CAHOJ POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS