

15-153-05220-00-05

6 031428

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER ~~15-153-30052-00-00~~

SEC. <sup>4</sup> T <sup>1</sup> S, R <sup>34</sup> W/EX

510 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

3911

Operator License # \_\_\_\_\_

Lease Name C.G. Kisling Well # 3 Cahoj 3

Operator: Rama Operating Co. Inc.

County Rawlins 138.77

Name & Address Box 159

Well Total Depth 4270 feet

Stafford, Ks. 67578

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: PM Day: 11 Month: Sept Year: 1990

Plugging proposal received from Lloyd

(company name) Rama (phone) \_\_\_\_\_

were: 8 5/8 set at 371 w/300 sks cwc. 5 1/2 set at 4270 w/200 sks.

Perf 3965 - 4115. Order 300 sks 65/35 popz 10% gel 500 lbs. hulls. Allied Cemt Co.

LaRue water trucks.

Perf at 2250 Kiowa. Hole open to prod. Perfs. Low fluid level.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:00PM Day: 11 Month: Sept Year: 1990

ACTUAL PLUGGING REPORT Sq annulus w/75 sks cement blend w/200 lbs. hulls

mixed into max psi 400 lbs. Close in psi 200 lbs. Sq 5 1/2 w/50 sks straight cement

followed w/175 sks cement w/500 lbs. hulls mixed into max psi 600 lbs. Close in psi 300 lbs.

Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
10-3-90  
OCT 3 1990

Remarks: Anhy 3013 - 3052; not perforated in this area because of depth of quality of deep water.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If ~~not~~ observe this plugging.)

DATE 10-8-90

INV. NO. 29559

*J.P.S.*

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow