

State of Kansas



15-153-05276-00-00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1964

1-2-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Sinclair Oil & Gas Co.

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sinclair Oil & Gas Company,

Complete Address: Box #456, Plainville, Kansas.

Lease Name: Bartosovsky Well No. 1

Location: CSW Sec. 8 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4339 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

449' -- 8 5/8" Surface pipe, cement circulated. 4339' -- 5 1/2" prod-

uction casing cemented with 200 Sx. Top perforations @ 4165'.

Plugged back to 4283'.

Sand well back to 4150' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" to 660' and circulate heavy gel mud, pull 5 1/2" to 600'  
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 440' and dis-  
Place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10  
Sx. cement to bottom of cellar. Very truly yours,

*A. L. Nichols*