



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1970
CONSERVATION DIVISION
Wichita, Kansas

15-153-20076-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Sramek Well No. 1

Location: CNE-NW Sec. 7 Twp. 1 Rge. (E)(W) 3/4

County: Rawlins Total Depth 4700' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

308'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1725'.

Circulate hole with heavy mud. Pull DP to 1950' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent