



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20089-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-15-1970
OCT 15 1970
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Argosy Petroleum Company,

Complete Address: 405 Walltowers East, Midland, Texas.

Lease Name: Sramek Well No. A-2

Location: CSW-SE Sec. 7 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4300' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

268'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1875'.

Circulate hole with heavy mud. Pull DP to 2100' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent