

State of Kansas



15-153-00037-00-~~00~~⁰²

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

*Rec'd
12-26-1963
KCC*

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Don Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well: Skelly Oil Co.,
Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: Box #649, McCook, Nebraska.

Lease Name: Cahoj Well No. C-1

Location: SE-SE-NE. Sec. 8 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4350 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

445' -- 8 5/8" Surface pipe, cement circulated.
4350' -- 5 1/2" cemented with 300 Sx. Well plugged back to 4187'.
Top perforations 3578' to 3584'.

Sand well back to 3570' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 660' and circulate heavy gel mud. Pull 5 1/2" to 600' and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 430' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. D. Nichols