

4-031764

9-16

27
R

15753-30063-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1966

SE NW /4 SEC. 11, 01 S, 34 W
3300 feet from S section line
3300 feet from E section line

Operator license# 30606

Lease Cahoj NE B Unit well # 2-1

Operator: Murfin Drilling Company, Inc.

County Rawlins

Address: 250 N. Water
#300
Wichita, Kansas 67202

Well total depth 4304 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 282 feet

139.88

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License#

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 16 Month: September Year: 92

Plugging proposal received from: John

Company: Murfin Drilling Company, Inc. Phone:

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:00A.M., Day: 16, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 282' w/175 sx. cwc. 5 1/2" set @
4303'w/100 sx. P.B.T.D. 4267'. Perf. 4149' - 4151'. Shot @ 2160' Kiowa.
Squeezed 5 1/2" with 350 sx. cement blend with 400# hulls mixed in to
Max. P.S.I. 600#. Close in P.S.I. 200#. Squeezed 8 5/8" w/100 sx.
cement blend w/100# hulls mixed in to Max. P.S.I. 300#. Close in P.S.I.
300#. Plug complete.

OCT 8 1992
10-8-92

CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES NO X

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TOBING , CASING X. Elevation: GL

I did X / did not] observe the plugging.

Carl Goodrow

DATE 10-19-92

HO

(agent)

INV. NO. 36499