

6 031413

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-05279-00-04
150 S of C NW SW
SEC. 9, T 1 S, R 34 W/E

1830 feet from S section line

4620 feet from E section line

Cahoj Unit 22

Lease Name F. E. Well # 4

Bartosovsky

County Rawlins 139.13

Well Total Depth 4281 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 367

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: Rama Operating Co., Inc.

Name & Address Box 159

Stafford, Ks. 67578

Abandoned Oil Well ~~##~~ Gas Well Input Well ~~X~~ SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 21 Month: August Year: 19 90

Plugging proposal received from Millard

(company name) Kelso (phone)

were: 8 5/8 set at 367 w/200 sks cwc 5 1/2 set at 4280 w/250 sks

TBTD 4185 Perf. 3970 - 4170. Order sand and common cement. Pull pipe, Order 300 sks

65/35 poz 8% gel, 500 lbs. hulls. Allied Cement Co. LaRue Water Trucks. Ran wireline hole open.

Plugging Proposal Received by Carl

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part xx None

Operations Completed: Hour: 7:00 Day: 21 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3920 w/5 sks common cement on sand w/bailer.

Recovered 1200 of 5 1/2 w/shot at 2200 + Sq 8 5/8 w/300 sks cement blend w/500 lbs.

hulls mixed into max psi 500 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1990

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(did) observe this plugging.

DATE 10-8-90

INV. NO. 29563

Carl Goodrow

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow