

6 031411

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153 05228-00-00

SE NE, SEC. 9, T 1 S, R 34 W/E

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Cahoj Well # 16

Operator: Rama Operating Co., Inc.

County Rawlins 138.80

Name & Address Box 185

Well Total Depth 4271 feet

Stafford, Ks. 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 373

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Poe Well Service License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 21 Month: August Year: 19 90

Plugging proposal received from Lloyd Fredrick

(company name) Rama (phone)

were: 8 5/8 set at 373 w/300 sks cwc 2 7/8 set at 4271 w/200 sks. Perf

3966 - 3972, shoot off and plug through tubing, order 300 sks 65/35 poz 8% gel,
500 lb.s hulls. Allied Cement Co. Larue water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30PM Day: 21 Month: August Year: 19 90

ACTUAL PLUGGING REPORT tubing parted 1850, tie onto tubing mix and pump down
tubing, circulated cement blend to surface tied on to 8 5/8 and sq w/300 sks cement blend
w/500 lbs. hulls mixed in to max psi 300 lbs. Close in psi 150 lbs.

Plug complete.

RECEIVED STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-8-90

INV. NO. 29571

File 9

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow