

To: 6 031427
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153 20,073 -00-01
C NW SW, SEC. 10, T 1 S, R 34 W/E

1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
3911
Operator License # _____
Operator: Rama Operating Co. Inc.
Name & Address: Box 159
Stafford, Ks. 67578

Lease Name Cahoj Well # 18
County Rawlins 139.42
Well Total Depth 4290 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well xx SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Ks.

Company to plug at: Hour: _____ AM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Lloyd

(company name) Rama (phone) _____

were: 8 5/8 set at 330 w/225 sks cwc. 5 1/2 set at 4289 w/300 sks. PBSD 4271.

Perfs 4015 - 4256. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls.

Allied Cement Co. LaRue water trucks.

Perf at 2280 kiowa hole open to prod pers. Low fluid level.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____

Operations Completed: Hour: 10:45AM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq annulus w/75 sks cement blend w/50 lbs.

hulls mixed in to max psi 400 lbs. Close in psi 200 lbs. Sq 5 1/2 w/75 sks straight
cement blend followed w/150 sks cement blend followed w/150 sks cement w/450 lbs. hulls
mixed into max psi 500 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: Anhy 3013 - 3052 = - elev. not perforated in this area due to depth and water
(If additional description is necessary, use BACK of this form) quality.

INVOICED
(did or not) observe this plugging.

DATE 10-8-90
INV. NO. 29565

Sub. S

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)