

4-031681

4-15  
15-153-05188-00-02  
205  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1959

SE SW NE /4 SEC. 09, 01 S, 34 W  
2970 feet from S section line  
1650 feet from E section line

Operator license# 30606

Lease Cahoj well # 15

Operator: Murfin Drilling Co., Inc.

County Rawlins

Address: 250 N. Water #300  
Wichita, Kansas 67202

Well total depth 4218 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 309 feet

137.08

Aband. oil well     , Gas well     , <sup>FNHR</sup> Input well X, SWD     , D & A     

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 15 Month: April Year: 92

Plugging proposal received from: John Turner

Company: Murfin Drilling Co., Inc. Phone:                     

Were: Order 425 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to production perf's. By Wireline.  
Shot @ 2365' Kiowa.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:20A.M., Day: 15, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 309' w/175 sx. 5 1/2" set @ 4208'  
w/125 sx. Perf's 3980' - 4176'. Squeezed 5 1/2" w/325 sx. cement blend  
w/400# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 300#.  
Squeezed 8 5/8" w/100 sx. cement blend w/100# hulls mixed in to Max.  
P.S.I. 300#. Close in P.S.I. 250#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD      Any plug: YES 3010 NO     

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X

Plugged through TUBING     , CASING     . Elevation: 3184

I did[ X ] / did not[      ] observe the plugging.

Carl Goodrow  
Wichita, Kansas  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1992  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 6-5-92

INV. NO. 35419

(agent)

Form CP-2/3

4-15 JUL 08 1992