

6 031429

API NUMBER 15-153-05192-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW SEC. 9, T 1 S, R 34 W/E

1650 feet from S section line

2970 feet from E section line

Cahoj 21

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Bartosovsky Well # 2

Operator: Rama Operating Co. Inc.

County Rawlins 141.70

Name & Address Box 159

Well Total Depth 4360 feet

Stafford, Ks. 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 446

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Ks.

Company to plug at: Hour: PM Day: 11 Month: 9 Year: 19 90

Plugging proposal received from Lloyd

(company name) Rama (phone) _____

were: 8 5/8 set at 446 w/300 sks cwc. 5 1/2 set at 4351 w/250 sks. PBDT 4186.

Perfs 4029 - 4270. Order 300 sks 65/35 poz. 10% gel. 500 lbs. hulls. allied Cement Co. LaRue water trucks.

Perf at 2365 Kiowa, hole open to prod perf. Low fluid level.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq annulus w/75 sks cement blend w/50 lbs. hulls mixed into max

psi 600 lbs. Close in psi 400 lbs. Sq 5 1/2 w/75 sks straight cement blend followed w/190 sks

cement blend w/500 lbs. hulls mixed into max psi 500 lbs. Close in psi 400 lb. Plug complete.

Log: Anhy 3013 - 3052 + - elev. infield. Not perf in this area because of depth and water quality.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____ (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-8-90

INV. NO. 29570

File S.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

10-3-90