

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20100-00-01
Spot: CNWNW , Sec/Twnshp/Rge: 9-1S-34W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: CAHOJ UNIT Well Number: 12
County: RAWLINS Total Vertical Depth: 4270 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: \$138.78
Surface Casing: Size 8.625 feet: 372
Production: Size 5.5 feet: 4267
Liner: Size feet:

Well Type: EOR UIC Docket No: E16643.5 Date/Time to Plug: 11/01/2001 9:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 450 sxs 60/40 pozmix - 10% gel - 400# hulls.
Order work string.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/01/2001 11:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 372' w/250 sxs cmt. 5 1/2" set at 4267' w/300 sxs cmt.
TOC 2959'. Exempt area.
Prod.Perfs 3987' - 4193'.
Ran tubing to 2100' - mixed and pumped 50 sxs cement blend with hulls.
Pulled to 1000' - mixed and pumped 50 sxs to circulate.
Tied onto 5 1/2" - squeezed with a total of 310 sxs cement blend with 900# hulls mixed in to Max. P.S.I. 300#.
Squeezed 8 5/8" with 40 sxs cement blend to Max. P.S.I. 300#.
Plug complete.
Bad 5 1/2" casing.

Remarks: LEASE ALSO KNOWN AS BARTOSOVSKY F.E. #7. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

RECEIVED
NOV 15 2001
KCC WICHITA

NOV 08 2001

INVOICED
DATE 11-15-01
INV NO. 2002060950

SKELLY OIL COMPANY #7 F. E. BARTOSOVSKY 9-1-34W
 DENVER, COLO. C NW NW
 CONTR GABBERT-JONES, INC. CTY RAWLINS

GEOL _____ FIELD CAHOJ
 E 3097 KB CM 11/27/70 ^{CARD}ISSUED 1/7/71 IP P 14 BO + 20% WTR
 LANS 4181-93
 API 15-153-20,100 GR 34.6

SMP	TOPS	DEPTH	DATUM	
				8 5/8" 372/250sx; 5 1/2" 4267/300sx
SC		2941	+ 156	NO DSTS
TOP		3788	- 691	
OREAD		3871	- 774	
DOUG		3948	- 851	MICT, CO TO 4245 PBTD, PF 36/4181-93
LANS		3987	- 890	'J'ZN 500 ACID SWB LD & SWB 1 1/4 BOPH N/W
LID		4268	-1171	(ONLY ZONE PERFORATED)
RTD		4270	-1173	NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS