

6 031196

API NUMBER 15-

12-6 15-153-05195-00-01
153-97,689

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NW, SEC. 16, T 1 S, R 34 W7E

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Cahoj Well # 39

Operator: Texaco Inc. for Texaco Prod. Inc. County Rawlins

142.19

Name & Address Box 2420

Well Total Depth 4375 feet

Tulsa, Ok. 74102

Conductor Pipe: Size feet

RECEIVED
STATE CORPORATION COMMISSION
01-18-1989
JAN 18 1989

Casing: Size 9 5/8 feet 450

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated E 16643

Plugging Contractor G. J. Titan License Number

CONSERVATION DIVISION
Wichita, Kansas

Address Oakley

Company to plug at: Hour: PM Day: 6 Month: Dec Year: 19 88

Plugging proposal received from Lloyd

(company name) Texaco (phone)

were: 9 5/8" set at 450' w/300 sks cwc. 5 1/2" set at 4367' w/250 sks.

PBTD 4329'. Perf 4055' - 4244'. Shots below Dakota at 2225'. Order 100 sks common cement

350 sks. 65/35 Poz 10% Gel 2% Dical. B. J. Titan Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00PM Day: 6 Month: December Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 2365'. Pumped 41 bbls slurry of

cement blend followed with 100 sks common cement w/Hulls mixed in. Laid down tubing to

T.O.C. Circulated w/cement blend to surface. Squeezed 5 1/2" to max psi 400#. Close in psi

200# w/350sks cement. Squeezed 9 5/8" w/100 sks. To max psi 500#. Close in psi 200#.

Plug complete.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby authorize you to serve this plugging.

DATE 1-20-89

INV. NO. 22719

12-6

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow