

To: 6 031431
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-153-05288-00-00 =
NE SW , SEC. 16, T 1 S, R 34 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: Rama Operating Co. Inc.
Name & Address Box 159
Stafford, Ks. 67578

2087 feet from S section line
3348 feet from E section line
Lease Name Cahoj E Well # 3
Cahoj #42

County Rawlins 142.87
Well Total Depth 4396 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well XX Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number
Address Russell, Ks.

Company to plug at: Hour: PM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Lloyd
(company name) Rama (phone)

were: 8 5/8 set at 371 w/300 sks cwc 5 1/2 set at 4395 w/200 sks. PBDT 4216.
Perfs 4094 - 4318. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls.

Allied Cement Co. Larue water trucks.
Shot at 2240 Kiowa hole open to production perfs. Low fluid level.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq annulus w/20 sks cement blend to max psi
500 lbs. Close in psi 500 lbs. Sq 5 1/2 w/75 sks cement blend followed w/175 sks.
Cment blend w/500 lbs. hulls mixed into max psi 700 lbs. Close in psi 300 lbs. Plug
complete.

RECEIVED
STATE CORPORATION COMMISSION
10-03-1990
OCT 3 1990

Remarks: Anhy 3013-3052 = - altitude in area not perforated due to depth and
water quality.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-8-90
INV. NO. 29561

J.S.

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)