

6 031432

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-153-05231-00-01

C SW SW, SEC. 16, T 1 S, R34 W/E

766 feet from S section line

4651 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Cahoj E Well # 2 #55

Operator: Rama Operating Co. Inc.

County Rawlins 143.00

Name & Address Box 159

Well Total Depth 4400 feet

Stafford, Ks. 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well ~~✓~~ Gas Well Input Well ~~X~~ SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Lloyd

(company name) Rama (phone)

were: 8 5/8 set at 370 w/300 sks cwc. 5 1/2 set at 4400 w/250 sks. PBTD 4303.

Perfs 4135 - 4324. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls. Allied Cement Co.

Larue Water Trucks. Shot at 2348 Kiowahole open to production perfs low fluid level.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 2:15PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq annulus w/20 sks cement blend locked up at 400 lb.

Blew out head packing. Sq 5 1/2 w/75 sks straight cement blend followed w/165 sks cement blend

w/450 lb hulls mixed into max psi 300. Close in psi 150 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION 10-3-1990 OCT 3 1990

Remarks: Anhy 3031 - 3052 +- elev. in area not perforated due to depth and water quality.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-8-90

INV. NO. 29560

J.H.S.

Signed Carl Goodrow