

10-22-87 15-153-20048-00-00

API NUMBER 15- 1969

SE SE, SEC. 16, T 1 S, R 34 (W)

663 feet from S section line

662 feet from E section line

Lease Name Cahoj Well # H-2

County Rawlins 142.19

Well Total Depth 4375 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 363

To: 6 030984
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Operator: Halliburton Oil Prod Co.

Name & Address Box 10

Stafford, Kansas 67578

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 22 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8" set at 363' w/275 sks cwc. 5 1/2" set at 4372' w/200 sks. PBTD 4342'.

Perf 4165' - 4261'. Order sand and Common Cement. Shoot and pull pipe. Order

200 sks Econolite 65/35 Poz 10% Gel 2% Dicel. Halliburton Cement Blend. 5 sks

Hulls. LaRue Water Turck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:40AM Day: 22 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4110' w/5 sks Common Cement on sand w/bailer.

Shots at 2100' 2000' 1900'. Recovered 1900' of 5 1/2" casing. Squeezed 8 5/8"

w/275 sks Cement Blend w/5 sks Hulls mixed in to Max Psi 300#. Close in Psi

150#. Plug complete.

STATE CORP. 11-30-1987
153 3015

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 12-4-87

INV. NO. 19108