

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05286-00-00
Spot: SENWSW Sec/Twnshp/Rge: 16-1S-34W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: TEXACO CAHOJ UNIT Well Number: 43
County: RAWLINS Total Vertical Depth: 4398 feet

Operator License No.: 6033
Op Name: MURFIN DRILLING CO.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 367 300 SX CMT
Production: Size 5.5 feet: 4393 250 SX CMT **\$142.94**
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/29/2001 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 463-6781

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/29/2001 1:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 367' w/300 sxs cwc. 5 1/2" set at 4393' w/250 sxs.
Prod.Perfs 4090' - 4316'. PBSD 4352'.
Casing holes at 1641' to 1949' squeezed with 375 sxs and circulated out 8 5/8".
Squeezed 5 1/2" with 340 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 250#. Held.
Plug complete.

RECEIVED
09-11-2001
SEP 11 2001
KCC WICHITA

Remarks: DRILLED AS CAHOJ E-1 THEN RENAMED TEXACO CAHOJ UNIT 43. SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

INVOICED

DATE 9-11-01

INV. NO. 2002060449

Form CP-2/3

SEP 05 2001