

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-153-05291-00-00

API NUMBER None  
 LEASE NAME Cahoj Unit  
 WELL NUMBER 40  
 SPOT LOCATION 1874' FNL, 1920' FW  
 SEC. 16 TWP. 1S RGE. 34 (E) or (W)  
 COUNTY Rawlins  
 Date Well Completed 4-27-60  
 Plugging Commenced 6-6-84  
 Plugging Completed 6-7-84

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Getty Oil Company  
 ADDRESS 2705 Vine, Unit #4, Hays, Kansas 67601  
 PHONE # (913) 628-1039 OPERATORS LICENSE NO. 6237

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing-KC Depth to top 4200' bottom 4245' T.D. 4364'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Oil	4200'	4245'	8-5/8"	360'	None
				5 1/2"	4351'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. RIH w/ open-ended tbg. Tagged up @ 4183'. Spotted 40 sks 50-50 Poz w/ 6% gel from 4168-3710'. Pulled tbg to 3526'. Ran SLM & ck'd. top of cmt @ 3710'. Lowered tbg to 3694' & pumped 85 bbl gelled wtr down tbg. Pulled tbg to 361' & pumped 35 sks 50-50 Poz w/ 3% CaCl2 down tbg. Cmt circ to surf. Pumped 55 sks 50-50 Poz w/ 6% gel & 2 sks hulls down 8-5/8"-5 1/2" annulus @ 1 BPM & 200 psi. State pluggger was notified but declined to witness operations. Welded steel plate backfilled & leveled (If additional description is necessary, use BACK of this form.) location.

Name of Plugging Contractor Halliburton Services License No. 5287  
 Address Box 47, Oberlin, Kansas 67749

STATE OF Kansas COUNTY OF Ellis, ss.


Frank Renard

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the Commission are true and correct, so help me God.

RECEIVED  
 06-28-1984  
 JUN 28 1984

(Signature) Frank Renard  
 (Address) 2705 Vine, Unit #4, Hays, KS 67601



My Commission expires: 9-9-84

before me this 27th day of June, 19 84  
Bobbie Schipper  
 Notary Public