

6-090476

1-22

11
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,380-00-00

SE SW SE /4 SEC. 36, 02 S, 23 W
415 feet from S section line
1665 feet from E section line

Operator license# 30885 Lease Lawrence Wiseman Well # 1

Operator: Lundvall Oil & Gas County Norton

Address: 1008 9th Street Well total depth 3655 feet
Greeley, Colorado 80631 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 271 feet

118.78

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Red Tiger Drilling Company License# 5302

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 21 Month: January Year: 1992

Plugging proposal received from: Walt Oden

Company: Red Tiger Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3552 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1820 feet " 20 " Mousehole:

3rd plug @ 1125 feet " 100 "

4th plug @ 320 feet " 40 "

5th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:00 PM, Day: 22, Month: January, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 205 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2226 GL, Anhydrite depth: 1808 - feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did penetrate Arbuckle, cemented by Allied Cementing Company

I did observe the plugging. Ed Schumacher

DATE 2-18-92

Ed Schumacher
(agent)

INV. NO. 34580

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1992
CONSERVATION DIVISION
WICHITA, KANSAS
2-12-92