

To: **6 031551**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-21
API NUMBER 15-137-20,158-00-00 **1982**

C/SE NE, SEC. 30, T 2 S, R 24 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050

Lease Name Thiele Well # 1

Operator: Hurmon Corporation
Name & Address 400 One Main Place
Wichita, Kansas 67202

County Norton **123.82**

Well Total Depth 3810 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 21 Month: 6 Year: 19 91

Plugging proposal received from Poe

(company name) Poe Well Service (phone) _____

were: 8 5/8 set @253' w/175 sxs. circ. 4 1/2 set @ 3809' w/125 sxs. PBD 3768

Perfs. 3749'-51 Order 300 sxs. 65/35 poz.- 10% Gel. 500# Hulls.

Halliburton Cement Company. Hole open through perfs. operating well with rods and tubing just removed. 'Shots @ 1300' and 2040'.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 P.M. Day: 21 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/200 sxs. cement blend w/500# Hulls.

Mixed in to max. P.S.I. 700# Close P.S.I. 700#. Squeezed 8 5/8 w/100 sxs. cement.

Blend to max P.S.I. 350#. Close in P.S.I. 350#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 01 1991

17-1-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

DATE JUL 22 1991

INV. NO. 32329

6-21