

To: **6 031183**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corp
Name & Address 400 One Main Place
Wichita, Ks. 67202

10-12
API NUMBER 15- 137-20,179 -00-00
C NW SW, SEC. 29, T. 2 S, R. 24 W/EX
1980 feet from S section line
4620 feet from E section line

Lease Name Foley Well # 1

County Norton **124.18**

Well Total Depth 3821 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Poe Servicing Inc. License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 12 Month: Oct Year: 1988

Plugging proposal received from Ed Pos

(company name) Poe Servicing Inc. (phone)

were: 8 5/8" set at 280' w/185 sks 4 1/2" set at 3820' w/150 sks.

PBTD 3791'. Perfs 3762' - 3772'. Shots at below Dakota 1300' and at Anhy 2000'. Order

200 sks 65/35 Poz 10% Gel 2% Dicl 500# Hulls. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☒ None ☐

Operations Completed: Hour: 5:02PM Day: 12 Month: Oct Year: 1988

ACTUAL PLUGGING REPORT Ran tubing to 2166'. Circulated cement up 4 1/2" casing
and up the 8 5/8" annulus to surface. Laid down tubing. Tied onto 4 1/2" casing.

Closed in 8 5/8" casing. Squeezed 4 1/2" and 8 5/8" to 650#. Max psi closed in at 300# psi.
w/total of 200 sks cement w/500# Hulls mixed in. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:

(If additional description is necessary, use BACK of this form)

INVOICED
I hereby certify that I have observed this plugging.

DATE 1-5-89

INV. NO. 23482

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow