

6 031531

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 137-20,344 00-00

W/2 E/2 SW, SEC. 33, T 2 S, R 23 W/Ex

1320 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name LeCount Well # 1

Operator: Viking Resources Inc.

County Norton 117.09

Name & Address 105 S. Broadway Suite 1040

Well Total Depth 3603 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 25 Month: April Year: 19 91

Plugging proposal received from Monte

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8 set at 252 w/150 sks. 4 1/2 set at 3598 w/150 sks. PBDT 3541.

Perf 3520 - 24. Order sand and common cement Pull pipe. Order 225 sks 65/35 poz 10% gel. 500 lbs. hulls. Allied Cement Co. LaRue Water Trucks. This well was sq three times and ran wireline to 900. Hole open into 4 1/2 casing.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15PM Day: 25 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3470 w/4 sks common cement w/bailer.

Recovered 813 of 4 1/2 w/shots at 2000, 1800, 1600, 1200, 1000.

Sq 8 5/8 w/225 sks cement blend w/500 lbs. hulls mixed into max psi 600 lbs.

Close in psi 300 lbs. Plug complete.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
6-7-91

JUN 07 1991

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
Please observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 6-18-91

INV. NO. 32181