

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

20290
API NUMBER 15-137-~~20890~~00-00

NE, SEC. 18, T 2 S, R 23 W/E

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5255

LEASE NAME Bright WELL # 1

OPERATOR: Mc Guinness Oil Co.
NAME & ADDRESS 1026 Union Cent. Bldg.
Wichita Ks.

COUNTY Norton

WELL TOTAL DEPTH 3710 FEET 120.58

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 211

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL D&A

OTHER WELL AS HEREINAFTER INDICATED 5140

PLUGGING CONTRACTOR Red Tiger LICENSE NUMBER 5302

ADDRESS 1720 Ka. State Bank Bldg. Wichita Ks.

COMPANY TO PLUG AT: HOUR: AM DAY: 9 MONTH: 7 YEAR: 19 83

PLUGGING PROPOSAL RECIEVED FROM Ken Iyle

(COMPANY NAME) Red Tiger (PHONE) 316 263.1201

WERE: Order 210 sx cem. 54/50 pozmix 6% gel 3% cal. 4.
1 sx hulls 1-8 5/8 plug

Heavy mud between all plugs

Pump cem. down drill pipe

Elev. 2436 Anhydrite 1985-2020 Arbuckle 3700

Dakota 1500 PLUGGING PROPOSAL RECEIVED BY Val R Balthazor
936 = 1230 (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 9 MONTH: 7 YEAR: 19 83

ACTUAL PLUGGING REPORT _____

1st plug 25 sx @ 3700

2nd plug 25 sx @ 2000

3rd plug 100 sx @ 1230

4th plug 40 sx @ 220 1 sx hulls push plug to 40'

5th plug 10 sx @ 40

REMARKS: 10 sx rat hole.

cementing co. Halliburton

I (DID DID NOT) OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION
7-18-83
JUL 18 1983
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 7-26-83
INV. NO. 4951-W

SIGNED Val R Balthazor
(TECHNICIAN)

FORM CP-2/3
REV. 6-83