

4-031838

6-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,388-00-00

SW SW SW /4 SEC. 05, 02 S, 24 W
330 feet from S section line
330 feet from E section line

Operator license# 31217

Lease Blickenstaff well # 1-5

Operator: Chaco Energy Company

County Norton

Address: P.O. Box 1587
Denver, Colorado 80201

Well total depth 3796 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 289 feet

123.37

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: June Year: 93

Plugging proposal received from: Gary

Company: A.L. Abercrombie Phone:

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.
Allied Cement Company.
Condition hole before plugging.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:30A.M., Day: 21, Month: June, Year: 93

Actual plugging report: Spot plugs with drill pipe.
1st. plug 25 sx. @ 2070'.
2nd. plug 100 sx. @ 1300'.
3rd. plug 40 sx. @ 340'.
4th. plug 10 sx. @ 40' W.P.
Circulate 15 sx. in rathole.

Remarks: Anhy. 2064' - 2091'.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2536 GL

RECEIVED
STATE CORPORATION COMMISSION
AUG - 2 1993

I did did observe the plugging.

Carl Goodrow 8-2-93
DN (agent)

INVOICED
AUG 03 1993
DATE
INV. NO. 38231