

4 060189

3-23

344 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-137-20,374-00-00
SW NW, SEC. 35, T 2 S, R 24 W/EX

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Melroy Well # 1

Operator: Frontier Oil Company

County Norton 122.20

Name & Address 125 N. Market

Well Total Depth 3760 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXX

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address Wichita, KS

Company to plug at: Hour: 11:45PM Day: 23 Month: March Year: 19 91

Plugging proposal received from D.L. Finnessy

(company name) Red Tiger Drilling Co. (phone) _____

were: Order 190 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
4-25-91
APR 25 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Herb Deines

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXX

Operations Completed: Hour: 11:45PM Day: 23 Month: March Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2000' with 25 sxs. Anhydrite 1991-2019'

2nd plug at 1240' with 100 sxs. Dakota 937-1237'

3rd plug at 305' with 40 sxs. Surface pipe to 263'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

~~XXXXXX~~ did not observe this plugging.

DATE 5-9-91

INV. NO. 31774

Herb S.

Signed [Signature]

(TECHNICIAN)
Herb Deines