



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 9 1963

10-9-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Quattlebaum of National Drilling Co. has this

date requested permission to plug the following described well:

H. P. McLish  
 Mr. Quattlebaum guarantees payment of the plugging fee.

Operator's full Name: H. P. McLish,

Complete Address: 704 Patterson Building, Denver, Colorado.

Lease Name: Miller Well No. 1

Location: CSE-NW Sec. 31 Twp. 2 Rge. (E) (W) 24

County Morton Total Depth 3809 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Quattlebaum was instructed to plug the well as follows:

- 257' -- 8 5/8" Surface pipe, cement circulated,
- Circulate hole with heavy mud, set plug @ 550' and 20 Sx cement.
- " " 250' with 1/4 Sk hulls & 20 Sx cement.
- " " 40' with 1/2 Sk hulls & 10 Sx cement.

Very truly yours,

W. L. Nichols  
 Conservation Division Agent