

State of Kansas



15-137-20008-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
OCT 23 1967
10-22-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Incorporated,

Complete Address: 1620 Wichita Plaza, Wichita, Kansas.

Lease Name: Luckert Well No. 1

Location: CSE-NW Sec. 13 Twp. 2 Rge. (E)(W) 24

County Norton Total Depth 3710' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
Dakota section from 1710' to 1545'.

Circulate hole with heavy mud. Pull DP to 1740' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichol
Conservation Division Agent