



15-137-30063-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1965
10-4-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. R. G. Smith of Richard G. Smith has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Richard G. Smith,

Complete Address: 227 Beacon Building, Wichita, Kansas.

Lease Name: Miller Well No. 1

Location: CSE-SE Sec. 25 Twp. 2 Rge. (E)(W) 25

County Norton Total Depth 3795 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Smith was instructed to plug the well as follows:

257' -- 8 5/8" Surface pipe, cement circulated with 275 Sx.???

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

" " 240' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

A. L. Nichols

Conservation Division Agent