

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-137-00270-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1963

CONSERVATION DIVISION
Wichita, Kansas

12-30-63

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Walter Sauvage of Sauvage Drlg. Inc., has this
date requested permission to plug the following described well:

Mr. Sauvage guarantees payment of the plugging fee.

Operator's full Name: Sauvage Drilling Company, Inc.,

Complete Address: 106 So. Rodhauer, Oberlin, Kansas.

Lease Name: Preston Well No. 1

Location: NW-NW-NW Sec. 23 Twp. 2 Rge. (E) (W) 25

County Norton Total Depth 3825 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sauvage was instructed to plug the well as follows:

270' -- 8 5/8" Surface pipe, cement circulated with 155 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

" " 260' with 1/4 Sk. hulls &
20 Sx. cement.

" " 40' with 1/2 Sk. hulls &
10 Sx. cement.

Very truly yours,

H. L. Roberts