


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-137-00242-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Norton County. Sec. 35 Twp. 2 Rge. (E) 25 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Cities Service Oil Co.
Lease Name Young "C" Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 5-13-57 19
Application for plugging filed 5-13-57 19
Application for plugging approved 5-15-57 19
Plugging commenced 5-13-57 19
Plugging completed 5-13-57 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy rotary mud to 310' of surface, set plug, dumped 1/2 sx hulls, spotted 20 sx cement on plug. Fill hole to 40' of surface with heavy mud, set plug at 40' with 1/2 sack hulls. Mixed 10 sacks cement, filled to 3' of surface. Mud and dirt to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann & Johnson
Address Evansville, Indiana

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. M. Hardin (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin

Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1957

My commission expires March 12, 1959

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC. 35 T. 2 R. 25W
BOOK PAGE 13 LINE 3

5-21-57

WELL RECORD

15-137-00242-00-00

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 1 FARM Young "C"

LOCATION 330' N. & 330' E. of Center, Section 35, Township 2, Range 25 N.,

ELEV. 2513 (2510 Gr.) CO. Norton STATE Kansas

IP. Dry hole. F. & A. May 13, 1957.

PERFS.

FRAC. ACID None

T.D. 3810' PBD. GRAV/GOR.....

DRLG. COMM. April 29, 1957 COMP. May 13, 1957 CONTRACTOR Lohmann-Johnson Drig. Co., Inc.

CASING RECORD:

8-5/8" at 320' with 250 ex. con.

Formation Record:

sand, shells and shale	G-850
shale	1480
shale and shells	1950
shale	2049
anhydrite	2078
lime and shale	2590
lime	2647
lime and shale	2778
lime	2874
lime and shale	3015
lime	3540
lime and shale	3575
lime	3716
shale	3770
lime and shale	3780
cored shale (rec. 4')	3785
cored sand & lime (rec. 5')	3790
lime, sand and shale	3799
granite wash	3807
granite	3810 T.D.

Howard	3224
Severy Sand	3295
Topoka	3320
Hechner	3435
Dodge	3464
Lensing	3478
Base Kansas City	3671
Gorham Sand	3777
Reagan	3795
Granite Wash	3799
Granite	3809
Pen.	1'
T. D.	3810

Slope Tests (Syfo):

500'	-	00
1000'	-	10
1500'	-	10
2000'	-	00
2500'	-	10
3000'	-	10
3500'	-	00

FILED
COMMISSION

7-7/8" Rotary hole.

CON. DIVISION
1957

5-21-57

PLUGGING
SEC. 35 T. 2 R. 25W
BOOK PAGE 13 LINE 3