


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-137-30063-00-00

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Norton County, Sec. 25 Twp. 2S Rge. 25 (EX) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Richard G. Smith
Lease Name Miller Well No. 1
Office Address 227 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 26 1965
Application for plugging filed September 26 1965
Application for plugging approved September 26 1965
Plugging commenced September 26 1965
Plugging completed September 26 1965
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil, clay & gravel	water	0	250	8 5/8"	275	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1. Filled hole with heavy mud to 550 feet; displaced 20 sacks cement through the drill pipe @ 550 feet
2. Filled hole with heavy mud to 250 feet; displaced 20 sacks cement through the drill pipe on top @ 1/2 sack hulls @ 250 feet
3. Filled hole with heavy mud to 40 feet; spotted 10 sacks cement @ 40 feet.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1965

CONSERVATION DIVISION
Wichita, Kansas

10-1-65

(Original filed with State Corporation Commission)


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ja-Le Contracting, Inc
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard G. Smith

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard G. Smith
227 Beacon Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of September, 1965



August 27, 1969

Janice Johnson

Notary Public.

15-137-30063-00-00

DRILLERS' LOG

OPERATOR: Richard G. Smith
227 Beacon Building
Wichita, Kansas

LOCATION: Miller No. 1
C SE SE Section 25, Township 2 South, Range 25 West,
Norton County, Kansas

CASING RECORD: 8 5/8" @ 275 feet cemented with 275 sacks cement

ELEVATION: 2488 K.B.; 2486 D.F.; 2483 G.L.

CONTRACTOR: Ja-Le Contracting, Inc., Great Bend, Kansas

COMMENCED: September 16, 1965

COMPLETED: September 26, 1965

TOTAL DEPTH: 3,795 feet

PRODUCTION: Completed as DRY HOLE, September 26, 1965

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1965
10-1-65
CONSERVATION DIVISION
Wichita, Kansas

L O G

(Measurements from top of rotary bushing to bottom of formation by driller)

Soil, gravel & clay	0- 250	Lime (Lansing-Kansas City)	3464-3652
Clay, shale, & sand	250-1700	Lime & shale	3652-3732
Sand & shale	1700-2100	Shale (Conglomerate)	3732-3769
Shale & lime	2100-3230	Granite Wash	3769-3790
Lime (Topeka)	3230-3418	Granite	3790-3797
Shale (Heebner)	3418-3425	Rotary Total Depth	3797
Lime & Shale	3425-3464		

The undersigned, Richard G. Smith, hereby certifies that the above log is a true and correct log of the formations encountered during drilling the above well as reflected by the daily drilling reports.


Richard G. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Before me, the undersigned, a Notary Public, within and for said County and State, on this 28th day of September, 1965, personally appeared Richard G. Smith, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.


Notary Public

My Commission Expires: August 29, 1969

